



Sales Quote

INDUSTRIAL BUSINESS INTL CORP

1580 Sawgrass Corporate Parkway
 Suite 130, Sunrise, FL 33323
 Tel: 954-302-3187, 315-4781
 Fax: 954-838-7746
 E-mail: ibicorp@intech-ie.com
 Tax Certificate No. 16-8012998465-1

Quote # IBI-2026-0033A
Date: Mar 11, 2026
Customer ID LINDE - INVEGAS

Bill To:
INDUSTRIAS VENEZOLANA DE GAS – INVEGAS Av. Principal Zona Industrial Santa Rosalia, Cagua Edo Aragua, Venezuela Att: Maryori Carrizales, María Morales maryori.Carrizales@linde.com

Ship To:
<i>Custom Agent to be informed at Maiquetia Airport, Venezuela</i>

Your #	Our #	Sales Rep	CIF	SHIP VIA	Terms	Validity
RC20007671	IBI-2026-0033 /65852600	L. Zuñiga W. Brito	Maiquetia Airport	BWPPD	See below	60 days
Item	Qty	Units	Description	Unit Pr (US\$)	Total (US\$)	
1	1	Eqp	CHROMALOX Gas Heating System Model GCHIB-27-100P-E4XX 100 KW, 480 V, 3 Ph Total Length 131 " (332.74 cm), Heating Length (269.24 cm), Includes Carbon Steel Flange, Elements in Incoloy 800 Carbon Steel Sch 40 Shell, Fittings, Inlet and Outlet Nozzles Carbon Steel Terminal Box 3 wires, 3 circuits Current-day Chromalox equivalent to 1994 ELTRON CHROMALOX circulation heater, E4 terminal housing. Please see attached document for heater data sheet. Need process conditions to be able to verify sheath/shell temps, pressure drop.	US\$ 167,540.00	US\$ 167,540.00	
2	1	Eqp	CHROMALOX Control and Power Panel Model PCA-126-CC-XX66 460V-480V Three Phase Amperage is rated up to 126.0 total amps and has 3 fused branch circuit(s). Short Circuit Current Rating: 5kA Third Party: This assembly has UL/cULus certification. Operating Ambient Temperatures: 0F (-18C) min and 104F (40C) max ambient temperature. Extreme sun exposure with higher ambient temperatures may require shading be installed to avoid overheating during full load operation. ENCLOSURE This PCA has an enclosure with exterior dimensions of 36"H x 36"W x 12"D (914mm x 914mm x 305mm) Rated for NEMA 4 / IP66 and has a Powder Coated Steel exterior CONTROLS Power Control: Contactor Power Control Process Control Type: Customer Supplied Signal (120 VAC) Over Temperature Control Type: 6050-1RA10 (1/16 DIN) Qty: 1 Shutdown Contactor, Fused Control Power Transformer, (3) terminal landings for 110-130V 1 amp inline relay signal shutdown. INCLUDED OPTIONS AND PACKAGES	US\$ 12,795.00	US\$ 12,795.00	



		<p>Outdoor Location Package with Anti-Condensation Heater with Adjustable Thermostat and Weatherproof Gasketing</p> <p>OTHER DETAILS</p> <p>Mounting Method: Wall mounted utilizing the designated locations.</p> <p>Single door opening for interior access</p> <p>Electrical entry and sensor input is located on the bottom and electrical exit is located on the bottom of the assembly with the designated area marked.</p> <p>STATUS/ALARM INDICATIONS</p> <p>Overtemp Alarm - Pilot Light, Heater Trip</p> <p>Panel Power On - Pilot Light</p> <p>Heater Enabled - Pilot Light</p> <p>Interlock Shutdown - Heater Tri</p> <p>Note: On-site training, start-up, & commissioning services are available from the Chromalox Service group.</p>		
		<p>Delivery Time</p> <p>Approval Drawings: 6 – 8 weeks ARO&P (After Reception Order and Payment)</p> <p>Manufacturing Lead Time: 6 – 8 weeks ARAD (After Receive Approval Drawings)</p> <p>Shipping and Handling: 2 wks</p> <p>Payment Terms</p> <p>Prepayment 100% with your Order</p> <p>Volume & Weight</p> <p>Estimated Gross Weight: 1,050 Lbs Heating Sys, Control Panel 210 Lbs</p> <p>Estimated Gross Volume: To be advised</p> <p>Cci: Williams Brito – INTECH Plcrz</p>		

PLEASE TRANSFER TO OUR ACCOUNT AT:
 Branch Banking & Trust Co.
 450 North Pine Island
 Plantation, FL 33324
 Account #: 0140953040
 ABA# 053-101-121
 Routing/Transit Number: 2631-9138-7
 Swift Code: BRBTUS33

THANK YOU FOR YOUR BUSINESS

Subtotal	US \$	180,335.00
Freight	US \$	Included
Insurance	US \$	Included
Docs.	US \$	-
TOTAL	US \$	\$ 180,335.00